

JOHN

Hurricane Ian

Atlas Fence Company, Inc.
10806 SW County Road 761
Arcadia, FL 34269
941-628-5147

Estimate

Date	Estimate #
4/30/2026	7022

Name / Address
23465 Harborview Rd. Punta Gorda, FL 33980

Project

Description	Qty	Cost	Total
Chain-Link Fence 236' of 6' tall and 25' of 4' tall, commercial grade 9 gage fabric, All post are schedule 40 thickness and set in concrete. 2" lines, 3" terminals for the 6' tall. 2.5" terminals for the 4' tall. 1 5/8" schedule 20 top rail tension wire installed on bottom of fence	1	5,692.00	5,692.00
Permit and filing fees	1	200.00	200.00
Removal and disposal of existing fence. Does not include tree / brush removal	1	800.00	800.00
A deposit of 30% is due before material is ordered. All deposits are non-refundable.			
Total			\$6,692.00

Atlas Fence Co. guarantees the workmanship for the period of one year from the date of install. Exclusions: This guarantee does not cover damage or material defects resulting from or in any way attributal to (a) neglect, (b) misuse, (c) abuse, (d) repair or alteration made by anyone other than Atlas Fence Co., (e) acts of God including, but not limited to, hurricanes, tornados, or severe weather, (f) lack of maintenance, (g) any cause other than workmanship defects attributable to Atlas fence co.

Atlas Fence Co. Is not responsible for any damage to sprinklers or other unmarked underground buried lines or objects. All Unpaid materials will remain property of Atlas fence in the event of nonpayment. Atlas fence is not responsible for the removal or disposal of trees, brush or existing fencing unless stated above. All deposits are Non refundable. Any changes are subject to a min \$300.00 change order fee.

By signing you are approving and accepting the price and terms listed.

Signature Pennis P. Hernandez
05/10/2026